



# Precision drift chambers (MDT) for ATLAS muon system.

**G.Chelkov JINR (Dubna)**

**DESY Zeuthen  
10 September 2002**




## **SOME GENERAL INFORMATION ABOUT ATLAS MUON SPECTROMETER.**

- 1. The quality of the muon measurement has been one of the guiding design criteria for the ATLAS experiment.**
- 2.. Muon spectrometer is the outer layer of ATLAS detector (average dimensions about 22 meters high and 44 meters long).**
- 3. For the muon trajectory the determination of 3 points in the muon track are the minimum needed.**
- 4. All together it lead us to the 5500 meters squared have to be covered by muon detectors or 400000 single drift tube detector, grouped in 1200 chambers.**



## ATLAS Detector






## Geneva - Stockholm





## Football ground





## HOW WE ARE CONSTRUCTING OUR CHAMBERS?

Given the large area of the muon spectrometer it was necessary to devise a cheap but precise means of capturing the data. Several types of coordinate detectors are used at the MUON system. I am talking now about MDT detectors only which covered the 98.6% of full area is covered by ATLAS Muon system ( 5500 from 5580m<sup>2</sup> ).

ATLAS has opted for a system of tubes (Monitored Drift Tubes chamber or MDT-chamber) grouped in 1200 chambers.

From mentioned above it should be clear that the process of MDT chamber construction and test is naturally divided into two parts:

- ***Tube assembling (wiring) and test.***
- ***MDT Chamber assembling and test***






## MDT Muon Chamber





## Chamber assembling scheme







## Procedure of drift tube wiring


**The incoming industrially produced components for tube wiring is:**

- 1. Thin wall precision Al – tubes;**
- 2. Gold plated 50  $\mu$  tungsten-rhenium wire;**
- 3. End-plug (which consist from end-plug body with high precision reference surface, wire holder for precise wire positioning, O-rings)**


**But as far as the performance of MDT muon system is determined by the performance of drift tubes and moreover there is no possibility to replace/repair single detector from the muon chamber the process of tube wiring and set of the tests must be relevant (QA/QC – procedure !!).**



## Drift tube construction and tube wiring



The scheme of the tube wiring is the following:





## Drift tube components (photo)







## Wiring Line





# DT Quality Control

## *PDT Working parameters:*

**Gas mixture: Ar(93)-CO<sub>2</sub>(7) at 3 Bar**  
**Voltage : 3120 V**

## *QC requirements:*

**Dark current at 3400 V 2nA/m**  
**Max count rate 20Hz/m**  
**Max gas leak 10<sup>-8</sup> Bar\*l/s**  
**Wire tension tolerance 17g**  
**Wire position tolerance 25μ**

## *Tests Sequence:*

- **Wire tension test ( wiring line )**
- **Wire position test ( X-ray )**
- **Gas leak & overpressure test**
- **HV&Functionality test**
- **Checking/packing/storing**
- **Wire tension ( chamber assembling zone )**

**Test rate : 120 tube/day**

## *Common solutions*


- Each tube have unique Id code
- All tests are computer-based
- All results are automatically stored in DB
- Bar-code scanner is used for Id reading





# Wire Tension Control

## Simple wire tension meter based on “magnetic” method





- Commercial PC extension board = 8 ADC & digital outputs
- Custom electronic module – DC source, amplifier and relay controlled via digital output.
- Wire may be connected either to DC source (send excitation pulse) or via amplifier to ADC
  - Wire excitation by current pulses
  - Digitization of the wire free oscillations
  - Oscillation spectrum extraction with FFT
  - Peak finding and base frequency extraction

No other equipment – even power is from PC  
Fully programmable – easy to adopt and build-in  
into any PC – based system



# Wire tension Control

## Accuracy





$\sigma = 12 \text{ mHz}$  at 50 Hz frequency



# Wire Tension Control

## PDT test results




	since 1.10.2000	overall
tubes tested	9130	10932
tubes rejected	31 0.3 %	583* 5.3%



# X-ray Test Station. Operation scheme.

Wire position tolerance :  $25\mu$


Operation scheme:





## X-ray Test Station (CCD)

And what do we get ? –  
image from CCD



**Reference wires completely define wire position  
with respect to V - groove**


Accuracy  $\sigma = 2\mu$





# X-ray Test Station (statistics)


## PDT test results



	since 1.10.2000	overall
tubes tested	8914	10710
tubes rejected	72 0.8%	149 1.4%



## X-ray Test Station (photo)






# Gas Leak Test (scheme)

Max leak :  $10^{-8}$  bar\*l/s = 0.3 mbar/day

## Measurement principles:



Equilibrium:

$$P = k \times L$$


P – pressure  
L - leak

- Use reference leak to define k !
- Use He as trace gas to avoid outgasing problem and make measurements less sensitive to system leak (no He in atmosphere)



# Gas Leak Test (set-up)

## Setup scheme:




Working condition in MS camera – UHV ( $\sim 10^{-6}$  mbar)  
Pressure inside torpedo  $< 1$  mbar

- While first “torpedo” is under measurement another one is being prepared - “mass production”
- Measurement time  $\sim 3$  min



## Gas Leak Test (photo)



10.09.02 DESY Zeuthen






# Gas Leak Test (LabView)


And how do we see the result? –

MS output for the  $0.25 \cdot 10^{-8}$  Bar $\times$ l/s calibration leak



Sensitivity - better then  $0.5 \cdot 10^{-9}$  bar $\times$ l/s  
Accuracy ~ 15 %


Real graphs with  
trace for 2 tubes.  
Last one have a  
leak about  
 $0.7 \cdot 10^{-8}$  bar $\times$ l/s





# Gas Leak Test (results)

## PDT test results



	since 1.10.2000	overall
tubes tested	8661	10395
tubes rejected	74 0.9%	111 1.1%



# HV & functionality test

**Leak current limit : 2 nA/m**

## Principles

- **Test a batch (up to 96) of tubes filled with standard gas mixture for a long time**
- **Slowly rise voltage while controlling current**
- **Drop voltage and rise it again if necessary for tube training**
- **Keep low humidity in test area**

**Based on CAEN 546 HV power supply module:**

- **96 channels , voltage is set by groups of 12**
- **Current in each channel is controlled with 1 nA accuracy**

**L3 amplifier, 32-channel discriminators and 16-channel CAMAC scalers are used to control count rate**

**Test procedure is automatic**

**Time consumption :**

**~1 hour for tube connection  
+ 1.5-12 hours for the test itself**



## HV test (photo#1)

How it looks like:




It is possible to test up to  
96 tubes simultaneously




## HV test (photo#2)

**HV board**



**connected  
DTs**









# HV test (results)

## PDT test results



	since 1.10.2000	overall
tubes tested	8585	10299
tubes rejected	29 0.3%	49 0.5%



## QC –final results

### Our current results

	overall		Since 1.10.2000	
test	tested	rejected	Tested	Rejected
Wire tension	10932	583 5.3%	9130	31 0.3%
X-ray	10710	149 1.4%	8914	72 0.8%
Gas leak	10395	111 1.1%	8661	74 0.8%
HV & rate	10299	49 0.5%	8585	29 0.3%
Overall				About 2.2%


Find us at <http://nuweb.jinr.ru/~dcbp/atlas/atlas.htm>



# MDT Production and tests

## Our current results


Dubna Tube Production (since 01.01.2001)





## Responsibilities and work organization.

The construction of the Muon Spectrometer is such a big effort that it is shared between many laboratories:






## Chamber assembling (1-st ruse).

***Two ruses widely used in the MDT chamber assembling procedure.***



***#1 - Assembling (gluing) precision components form non-very precision elements using high precision combs and glue***





## Chamber assembling (2-nd ruse).



**#2 Since deformation of such large (about 10 m<sup>2</sup>) object made form Al (not from marble!) can not be eliminated, one have to be able to control (and to compensate in a reconstruction procedure!) this deformation during all time period of chamber operation.**









# RASNIK





# MDT Production. Step#1


## Spacer assembling





## MDT Production. Step#2

### First layer gluing








## MDT Production. Final step

**Step#3 → Turn up-side down. 2nd layer gluing**

**Step#4 → Turn up-side down. 3d layer gluing**

**Step#5-7 → Turn up-side down. Next layer gluing**





## Authors (not all)



35



37



31



49



31



31




25



22



# Data collection system







## Workshop photos



10.09.02 DESY Zeuthen